



**Mary Harpley
Chief Executive**

**Chief Executives' Directorate
Civic Centre, Lampton Road
Hounslow TW3 4DN**

Councillor Tony Louki

Tony.louki@hounslow.gov.uk

Your contact: Customer Relations Team
Direct Line: 020 8583 5211
E-Mail: feedback@hounslow.gov.uk
Our ref: 26998-26999
Your ref: 14139230
Date: 02/06/2017

Dear Councillor Louki,

Re: Resurfacing of The Grove, Isleworth

We are writing with regard to your enquiry about early resurfacing of The Grove.

This road is split into two sections or two RSL's (Road section lengths). Each has been surveyed by an independent assessor since the start of the PFI contract on an annual basis. Each year the data returns on these RSL's show minimal defects and therefore they have fallen below our intervention levels (the point at which they are deemed in need of resurfacing).

If we can simplify the data collated in the last survey for you it would read as follows:

RSL 1. CO27/505_4D_01 The Grove – Harvard Road to Spring grove Road

RSL 2. CO27/515_4D_01 The Grove – London Road to Harvard Road

RSL Ref:	Major Chipping Loss	Major Cracking	Wheeltrack Cracking	Major Fretting	Transverse Cracks Severity 2	Minor Fretting	Localised Moderate Settlement	Percentage Defective
	M2	M2	M2	M2	No.	M2	M2	%
CO27/505_4D_01	48.02	191.52	101.64	0.7	15	6.33	2.01	11%
CO27/515_4D_01	191.46	81.59	45.33	2.99	13	3.19	6.7	9%

As you can see, there are minimal defects on each. As such there are no plans to resurface the road (either section) this year. Although there are some defects evident on each occasion, it has been found structurally sound with good skid resistance. Therefore, it is well below the level at which we would need to step in with a total treatment. As you may be aware we are

not required to treat every carriageway in the Borough under the terms of the contract, but please be assured that monies will be spent on those carriageways that are most in need of treatment in the first instance.

In the interim, the road is checked by our own inspectors on a regular basis and any defects deemed hazardous will continue to be picked up on assessment for remedial repair.

Going forward, data from the annual surveys suggests a projected treatment date for one of the RSL's on this road as being in the summer of 2018, although this is subject to change dependent upon deterioration rate and resulting data from the next annual survey and future surveys.

Section LP	Street Name	Location	Sqm Actual	Projected Treatment date	Treatment Type
C027/505_4D_01	THE GROVE	HARVARD RD TO SPRING GROVE RD	3,189	01/07/2021	FC-STREN&SEAL:4&5
C027/515_4D_01	THE GROVE	LONDON RD TO HARVARD RD	3,657	01/07/2018	CC-MS&SEAL:4&5

Thank you for your enquiry. Please do not hesitate to reply should you have any further questions.

Yours sincerely,

Customer Relations Team